

**City of Lewiston  
Vault Inventory/Assessment**

Date: June 20, 2016

Address: 700 Main

Owner/Business: Mike Haines / Diamond Shop

Property Line Known: \_\_\_\_\_ Investigation Needed: \_\_\_\_\_

Assessment Team:

Michelle Bly

David Witthaus, Photographer

Kris Brown

**Vault No:** \_\_\_\_\_

**Access:** Hatch

<b>Access Opening Dimensions</b>	<b>Feet</b>	<b>Inches</b>
Width	3	10
Height	2	11

Wood Hatch (not door) 3'2" off floor

<b>Vault Dimensions</b>	<b>Feet</b>	<b>Inches</b>
Width	9	10
Depth	12	2
Height (to bottom of beam)	6	8

<b>Beams</b>	<b>Feet</b>	<b>Inches</b>
Number of Beams	--	
Width (flange)	--	--
Depth	--	--
Height	--	--
Spacing (on center)	2 bays	

<b>Sidewalk Vault Opening Dimensions</b>	<b>Feet</b>	<b>Inches</b>
Width	3	0
Depth	3	0
Height	--	--

**Left Side Wall:**

Material: Stone

If Other: \_\_\_\_\_

Condition: Good

Comments: Mortared Stone

**City of Lewiston  
Vault Inventory/Assessment**

**Right Side Wall:**

Material: Stone If Other: \_\_\_\_\_

Condition: Good

Comments: Mortared stone

---

**Street Walls:**

Material: Stone If Other: \_\_\_\_\_

Condition: Good

Comments: Mortared Stone

---

**Building Walls:**

Material: Stone If Other: \_\_\_\_\_

Condition: Good

Comments: Mortared Stone

---

**Flooring:**

Material: Unknown If Other: \_\_\_\_\_

Condition: Unknown

Comments: Deeply covered with Rubble. Cannot ascertain condition or material.

---

**Ceiling:**

Material: Brick If Other: \_\_\_\_\_

Condition: Poor

Comments: Vault ceiling is shored with wood beams and posts in multiple locations.

---

**City of Lewiston  
Vault Inventory/Assessment**

**Sidewalk:**

Material: Concrete If Other: \_\_\_\_\_

Condition: Good

Comments: 3' x 3' steel plate opening. Unknown use.

---

**Beams:**

Material: Steel If Other: \_\_\_\_\_

Condition: Poor

Comments: Severely corroded in places. Typical roof construction, brick arches with steel beams.

---

Schematic(s) Attached: Yes

Current Use of Vault: Not in use.

Historic Value of Vault: See independent assessment.

---

**Overall Rating:**

At Time of Inventory: Poor (Based on shoring)

After Completion of All Inventories: Poor

**Additional Notes**

---

---

---

---

**This rating is based on visual observations of the various components of the vault including materials, conditions, etc. However, no structural analysis was performed, and the rating is not intended to indicate the structural integrity of the vault or sidewalk above.**